BRUHATH BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwarai Nagara Division, RR Nagara Zone.

ITEM - WAR DRAFT TENDER SCHEDULE-B

NAME OF THE WORK : Desilting of Drains at J.P Park Road from Mathikere Bus Stand to Mohankumar Nagara in ward no 17.

Sl No.	Description of Work	Unit	Qty	Rate	
				in Fig.	Words
1	Removing B.S. Slab of drain and Stacking	smtr	1566.00		
2	Earthwork in surface Excavation in Ordinary Soil for levelling & lowering the ground manually (Other than foundation of building culverts road drains & Trenches of pipe Lines & cables) & removing the exacavated stuff to a distance not exceeding 50m & lift upto 1.50m exacavated surface levelled & neatly dressed disposed earth to be levelled after breaking of clods & neatly dressed as per Specifications . As per direction of the Engineer incharge.	cmtr	637.20		
3	Refixing Stone slabs of drains and pointing in C.M 1:3	smtr	1566.00		
4	Providing a granite slabs of Selected quality roughly dressed and fixing in cement morter (1:6) including fixing curing etc., complete 10cms thick	smtr	454.00		
5	Conveying the exacavated debries and over burden earth etc., to a lead of 9 to 14kms distance by using private vehicle this includes the cost of loading and unloading charges etc.,	cmtr	620.00		

Executive Engineer,
Rajarajeshwari Nagara Division,
Bruhath Bangalore Mahanagara Palike.

DTS Approved